

K-3 65
R

API NUMBER 15- 185-22,577-0000
100' N of
E/2 E/2 SE, SEC. 33, T 24 S, R 15 W/E
1420 feet from S section line
330 feet from E section line

To: 1-120392
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 9705
Operator: Mid-American Hydrocarbon, Inc.
Name & Address: 114 East Avenue North
Lyons, KS 67554

Lease Name Doran Well # 2
County Stafford 146.12
Well Total Depth 4496 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 3 Month: 4 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4502' w/150 sx cement PRTD 4455' Perfs at 3900-4435' (5 sets) Elevation 2031' GL
1st plug sand back to 3850' with 5 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 P.m. Day: 3 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3850' and dumped 5 sx cement
on top of sand with bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 125 sx cement. Plugged through 8 5/8"-2" swedge.
Pumping pressure 0-750 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-17-90
INV. NO. 27860

observe this plugging.
CONSERVATION
WICHITA
Rec'd 4-6-90

Signed Steve Durrant (TECHNICIAN)