

1060945

APR 8 1987

43R

API NUMBER 15-185-22,424-0600

To; STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW, SEC. 33, T 24 S, R 15 W/R

1650 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9705

Lease Name Cummins Well # 1

Operator: Mid-American Hydrocarbon, Inc.
Name & Address: 114 East Avenue North
Lyons, KS 67554

County Stafford 146.97

Well Total Depth 4522 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling Inc. License Number 9421

Address Box 723, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 4 Year: 19 87

Plugging proposal received from Ruth

(company name) Boger Brothers Drilling Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2037' GL
Anhydrite 980'

1st plug at Arbuckle with 25 sx cement, 2nd plug at base Anhydrite plus 50' with 50 sx
cement, 3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 p.m. Day: 8 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 996' with 50 sx cement,

2nd plug at 350' with 50 sx cement,

3rd plug at 40-0' with 1 sx hulls, 1 wooden plug and 10 sx cement.

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

4-14-87

APR 14 1987

Signed Paul A. Luthi
(TECHNICIAN)

DATE 4-15-87

INV. NO. 16539

MAY 14 1987 CONSERVATION DIVISION
Wichita, Kansas JUL 0 8 1987

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 19 1987 month day year

API Number 15- 185-22,424

OPERATOR: License # 9705
Name: Mid-American Hydrocarbon, Inc.
Address: 114 E. Avenue North
City/State/Zip: Lyons, KS 67554
Contact Person: Kerry Davison
Phone: (316) 257-5111

SE NE SW East
Sec. 33 Twp. 24 S, Rg. 15 X West
1650
2970
Fl. from South Line of Section
Fl. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County: Stafford
Lease Name: Cummins Well # 1

CONTRACTOR: License #
Name: Unknown Boggs Bros. Drilling Inc.

Ground surface elevation NA feet MSL

Well Drilled For: X Oil SWD Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: X yes no
Municipal well within one mile: yes X no

If OWWO: old well info as follows: 316-792-8151
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 160
Depth to bottom of usable water 300

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 320

Conductor pipe required 0
Projected Total Depth 4600 feet

Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 3/12/87 Signature of Operator or Agent Title Agent/Geologist

For KCC Use:
Conductor Pipe Required feet: Minimum Surface Pipe Required 320 feet per Alt.
This Authorization Expires 9-12-87 Approved By 3-12-87

3-27-87 set 8 3/8 320'

SE NE SW East
Sec. 33 Twp. 24 S, Rg. 15 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 4600 feet depth with 25 sxs of .60/40. DQZ, .6% gel
2nd plug @ 350 feet depth with 10 sxs of .60/40. DQZ, .6% gel
3rd plug @ 40 feet depth with 10 sxs of .60/40. DQZ, .6% gel
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
Rathole with 15 sxs (b) Mousehole with 10 sxs

Vertical list of well parameters:
PUSHER: Ruth of Boggs Bros.
TD: 4532 FORMATION Arbuckle
SURFACE PIPE: 8 3/8 @ 8 3/8-335
ANHYDRITE: 980 ELEVATION 2037 Gd. 4-8-87
STARTING TIME & DATE: 11:30 AM 4-8-87
COMPLETION TIME & DATE: 1:30 PM
1st PLUG @ 996 FT. W/ 50 SX
2nd PLUG @ 350 FT. W/ 50 SX
3rd PLUG @ 40-0 FT. W/ 0 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 15 SX
CEMENT COMPANY Hall w/ 60/40 w/ 6%
TECHNICIAN S. Luthie

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1987
CONSERVATION DIVISION
Wichita, Kansas