

4-12 15-047-50022-0000 118 P

1-120405

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 5/27/55

N/2 NW SW, SEC. 4, T 24 S, R 16 W/E
2310 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111
Operator: Rockhold Engineering, Inc.
Name & Address: Box 698
Great Bend, KS 67530

Lease Name Hahn Well # 4
County Edwards 137.48
Well Total Depth 4230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering Inc. License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 12 Month: 4 Year: 19 90

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering (phone) 316-792-2506

were: 7" at 3829' Perfs at 3762-68'

1st plug sand 7" back to 3700' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls, 15 sx gel, 60 sx cement, 15 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 12 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3712' and dumped 7 sx cement on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Pumping pressure 0-600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services, Inc. Recovered 1923' of 7" casing. (Additional description is necessary, use BACK of this form.)

INVOICED

I did / did not observe this plugging.

DATE 4-24-90

Signed Russ Rankin (TECHNICIAN)

INV. NO. 27959

Rec'd 4-18-90