

4-12 15-047-00096-0000 119  
R

To: 1-120406  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/1/54

NW SE SW, SEC. 4, T 24 S, R 16 W/E  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5111

Lease Name Hahn Well # 1  
County Edwards 146.12

Operator: Rockhold Engineering, Inc.  
Name & Address Box 698  
Great Bend, KS 67530

Well Total Depth 4496 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 232

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 12 Month: 4 Year: 19 90

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3851' Perfs at 3770-3840'

1st plug sand back to 3720' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and  
150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 12 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3720' and dumped 5 sx cement  
on top of sand through bailer,  
2nd plug pumped into 10 3/4" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls and 150 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services, Inc. Recovered 2500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-90

INV. NO. 27958

Rec'd 4-18-90

Signed *Duan Rankin*  
(TECHNICIAN)