

1 010206

1-23-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A 15-185-20447-0000
C NW, SEC. 31, T 24 S, R 15 (W/E)
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Graybill Well # 1

Operator: Knighton Oil Company, Inc.
Name & Address 710 Petroleum Building
Wichita, KS 67202

County Stafford 141.86

Well Total Depth 4365 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 14 Month: 1 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4364' PBD 4320' Perfs at 4271-81'

1st plug pump to 4200',

2nd plug pump 3' sx hulls, 10 sx gel, .50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Glen Barlow and Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 23 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped to 4200' with 1 sx hulls, 50 sx cement, and 4 1/2" wiper plug. Used common cement. 1900 lbs. pressure.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

STATE CORPORATION COMMISSION

Rec'd
1-28-87 JAN 28 1987

Remarks: Recovered 1800' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied CONSERVATION DIVISION
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

(if additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-29-87

Signed [Signature]
(TECHNICIAN)

INV. NO. 16016