

3-8-88

To: 1 120078
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,985-0000

TECHNICIAN'S PLUGGING REPORT

SE SW NE, SEC. 24, T 24 S, R 15 W/X
2970 feet from S section line
1650 feet from E section line

Operator License # 3646

Lease Name Debusk Well # 1

Operator: Haven Energy Corporation
Name &
Address 7310 East Kellogg
Wichita, KS 67207-1695

County Stafford 144.95

Well Total Depth 4460 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 8 Month: 3 Year: 19 88

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4458' Perfs at 4184-92'

1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement. Light cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 8 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4130' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" with 350 lbs. hulls, 10 sx gel, 50 sx cement,

150 lbs. hulls, and 125 sx cement.

Pumping pressure 0-350 psi and shut in 100 psi.

Remarks: Used 65/35 Pozmix 6% gel by Howco. Recovered 2827' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1988
3-14-88
CONSERVATION DIVISION
WICHITA, KANSAS

(If you observe this plugging.

Signed Duane Purkin
(TECHNICIAN)

INVOLVED
DATE 3-16-88
INV. NO. 20111

QUADEL ENERGY CORPORATION &
BIG "J" PRODUCTION COMPANY, INC.
729 E. CENTRAL

REPLACEMENT CARD

24-24-15W
SE SW NE

WICHITA, KS 67211

#1 DEBUSK

CONTR SLAWSON DRILLING CO., INC. CTY STAFFORD

GEOL J.E. JESPERSEN


FIELD SUITER

ELV 2015 KB SPD 1/20/80 CARD ISSUED 6/12/80 IP OIL WELL

2010 GL

VIOLA 4184-4192

API 15-185-20,985



LOG	Top	Depth	Datum
HEEB		3586-1571	
BR LM		3732-1717	
LANS		3748-1733	
BKC		4012-1997	
MISS		4070-2055	
KIND SD		4095-2080	
VIOLA		4182-2167	
SIMP		4354-2339	
ARB		4432-2417	
LTD		4458-2443	
RTD		4460-2445	

8 5/8 " 275 / 250 SX, 4 1/2 " 4458 / 175 SX

DST (1) 3882-3910 (LKC) / 15-30-30-30, REC 70' MW, SIP
1296-1252, FP 34-34 / 45-56#

DST (2) 4088-4128 (KIND SD) / 15-30-30-30, REC 30' M, SIP
68-34#, FP 34-34 / 34-34#

DST (3) 4178-4190 (VIOLA) / 15-45-60-45, REC 220' HO&GCM,
270' FROGGY GSY O, SIP 1352-1185#, FP 79-102 / 113-181#

MICT - CO, PF (VIOLA) 17 / 4184-4192, SWB DWN GSO, POP, 3/
17/80

CORRECTION & INFO RELEASED: 3/17/83 - WAS OPERATIONS
SUSPENDED, ORIGINALLY FIRST REPORTED AS SE SW NW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS