

6-29 15-185-00312-0000

To: I 120272  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 10/19/56

NW NW SW, SEC. 29, T 24 S, R 15 W/EK

2310 feet from S section line

4950 feet from E section line

Lease Name Ackerman Well # 1

County Stafford 146.41

Well Total Depth 4505 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5540

Operator: Santa Fe Pipe & Supply, Inc.  
Name & Address Box 562  
Great Bend, KS 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 29 Month: 6 Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4300' PBSD 4224' Perfs at 3904-12'

1st plug sand back to 3850' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 p.m. Day: 29 Month: 6 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3850' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, and 120 sx cement.

Waited on welder. Welded plate and 2" connection on top of 8 5/8" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2520' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 7-5-89

INVOICED observe this plugging.

DATE 7-6-89

Signed Dean Rankin (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

INV. NO. 25221