

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20072-00-00
Spot: SESESE Sec/Twnshp/Rge: 10-23S-17W
358 feet from S Section Line, 346 feet from E Section Line
Lease Name: KASSELMAN Well #: 1
County: PAWNEE Total Vertical Depth: 4265 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2030		WITH 2 SX CMT
CIBP		4070		WITH 2 SX CMT
PROD 4.5		4263	0	WITH 200 SX CMT
SURF 8.625		262		WITH 210 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2015 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 4080' WITH 2 SX CMT. SET CIBP @ 2500' WITH 2 SX CMT. PERFORATE AT 1150' WITH 50 SX CMT. PERFORATE AT 300' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/17/2015 2:00 PM

KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4070' WITH 2 SX CMT. SET CIBP @ 2030' WITH 2 SX CMT. CEMENT BOND LOG RAN TO DETERMINE LOCATION & CONDITION OF CMT BEHIND 4 1/2" CASING. FOUND WELL SQUEEZED. BASE OF CMT AT 780'. CMT TO SURFACE FROM 780'-0'. PERFORATE 4 1/2" CASING AT 1300'. INJECTION TEST PERFORMED. PUMPED DOWN 4 1/2" WITH 90 SX CMT WITH 100# HULLS. MAXIMUM PRESSURE 650 PSI. SHUT IN. CMT TO SUFACE ON 4 1/2" X 8 5/8".

Perfs:

Top	Bot	Thru	Comments
4144	4148		
4130	4135		

KCC WICHITA
DEC 28 2015
RECEIVED
12-28-15

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed [Signature]
SA (TECHNICIAN)

RECEIVED
DEC 23 2015
KCC DODGE CITY

Form CP-2/3
920
12-30-15