

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23203-00-01
Spot: SESENEW Sec/Twnshp/Rge: 16-18S-26W
4195 feet from S Section Line, 2915 feet from E Section Line
Lease Name: BREIT OWWO Well #: 1-16
County: NESS Total Vertical Depth: 4650 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2040		WITH 400 SX CMT
PROD	4.5	4648	0	WITH 550 SX CMT
SURF	8.625	250		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2015 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 30 SX CMT & 12 SX GEL. PULL TBG TO 2190' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TEST BACKSIDE.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2015 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4402' & SPOT 12 SX GEL IN 36 BBLs. PUMP 30 SX CMT & 150# HULLS. PULLED TBG TO 2109' & PUMPED 150 SX CMT. CMT CIRCULATED BUT WAS FALLING. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#. 12/21/15: FOUND CMT AT 800'. PUMPED 50 SX CMT & CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4391	4394		

KCC WICHITA
DEC 28 2015
RECEIVED
12-28-15

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
SA (TECHNICIAN)

RECEIVED
DEC 22 2015
KCC DODGE CITY

No
12-30-15