

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21689-00-00
Spot: E2NWSWSE Sec/Twnshp/Rge: 29-26S-12W
990 feet from S Section Line, 2227 feet from E Section Line
Lease Name: BROWN Well #: 10
County: PRATT Total Vertical Depth: 4320 feet

Operator License No.: 33810
Op Name: WALCHER OIL, LC
Address: PO BOX 2026
BELLEVUE, WA 98009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		WITH 2 SX CMT
PROD	5.5	4318	1602	WITH 100 SX CMT
SURF	8.625	307		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2015 9:15 AM
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.
Proposal Rcvd. from: EDGAR SANCHEZ Company: AMIGOS WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4100' WITH 2 SX CMT. PLUG AT 740' WITH 15 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2015 10:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 3400' WITH 2 SX CMT. 12/10/15: AT 750' PUMP 40 BBL WATER, HOLE WOULD NOT LOAD. PUMP 15 SX GEL & 50 SX CMT. PARTIAL CIRCULATION AT END. SDON. 12/11/15: TAG AT 674'. PUMP 50 SX CMT AT 660'. PUMP 50 SX CMT AT 344'. PUMP 25 SX CMT AT 0-60'. GOOD CIRCULATION. HOLE STAYING FULL AT END.

Perfs:

Top	Bot	Thru	Comments
4142	4152		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

12-21-15

District: 01

Signed _____
(TECHNICIAN)

RECEIVED
DEC 17 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

12-30-15