

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20730-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 18-33S-40W
3118 feet from S Section Line, 4330 feet from E Section Line
Lease Name: SANTA FE UNIT Well #: 1-9
County: MORTON Total Vertical Depth: 5360 feet

Operator License No.: 34929
Op Name: WYNN-CROSBY OPERATING, LTD.
Address: 14241 DALLAS PKWY, STE 800
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5165		WITH 2 SX CMT
PROD	5.5	5356	0	WITH 225 SX CMT
SURF	8.625	1518		WITH 750 SX CMT

Well Type: EOR UIC Docket No: E23270.3 Date/Time to Plug: 12/10/2015 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: TIM HARPER Company: WYNN-CROSBY OPERATING Phone: (806) 330-0273

Proposed Plugging Method: SET CIBP @ 5165' WITH 2 SX CMT. PERFORATE AT 1550'. PUMP 50 SX CMT & 100# HULLS IN THE LAST 25 SX CMT. PERFORATE AT 550' & PUMP 300 SX CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2015 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5165' WITH 2 SX CMT. PERFORATE AT 1550'. PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 550'. PUMP 300 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5215	5225		

Remarks: **COMPLIANCE ISSIE: DENIED TA SI 10 YRS** USED CLASS A CEMENT BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: CSG

12-21-15

District: 01

Signed B. JB
SA

RECEIVED
DEC 11 2015
KCC DODGE CITY

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

DEC 21 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
NO
12-30-15
cc to UIC