

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21346-00-01
Spot: SWSW Sec/Twnshp/Rge: 32-30S-11W
727 feet from S Section Line, 4844 feet from E Section Line
Lease Name: CHAIN OWWO Well #: 1-32
County: BARBER Total Vertical Depth: 3746 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3661	2420	WITH 125 SX CMT
SURF	8.625	289		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2015 12:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 150# HULS & 30 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2015 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 150# HULLS & 30 SX CMT. SHUT IN AT 1200#. TAG TOC INSIDE 4 1/2" CASING AT 3210'. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 336' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3566	3576		
3556	3576		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

12-21-15

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)
SA

RECEIVED
DEC 10 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 21 2015
CONSERVATION DIVISION
WICHITA, KS
No 1220-15