

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21413-00-00
Spot: SESWNWSW Sec/Twnshp/Rge: 3-7S-28W
1448 feet from S Section Line, 546 feet from W Section Line
Lease Name: CAMPBELL Well #: 1
County: SHERIDAN Total Vertical Depth: 4510 feet

Operator License No.: 35245
Op Name: SUEMAUR EXPLORATION & PRODUCT
Address: 802 N. CARANCAHUA
CORPUS CHRISTI, TX 78401

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>SURF</u>	<u>8.625</u>	<u>333</u>		<u>200 sx</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/08/2015 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (785) 769-6103

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE Witness Type: NONE
Date/Time Plugging Completed: 11/08/2015 11:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report: _____ Perfs: _____

1st plug @2500 w/50 sx
2nd plug @1670 w/100 sx
3rd plug @385 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED

Plugged through: DP

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

DEC 14 2015

Received
KANSAS CORPORATION COMMISSION

DEC 30 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
12.30-15