

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21412-00-00
Spot: NESENWNE Sec/Twnshp/Rge: 18-7S-28W
692 feet from N Section Line, 1503 feet from E Section Line
Lease Name: OELKE Well #: 1
County: SHERIDAN Total Vertical Depth: 4460 feet

Operator License No.: 35245 String Size SURF 8.625 Depth (ft) 349 Pulled (ft) 220 Comments SX
Op Name: SUEMAUR EXPLORATION & PRODUCT
Address: 802 N. CARANCAHUA
CORPUS CHRISTI, TX 78401

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/23/2015 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (785) 769-6103

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2015 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report: Perfs:
1st plug @2522 w/50 sx
2nd plug @1711 w/100 sx
3rd plug @399 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED
Plugged through: DP

District: 04 Signed [Signature] (TECHNICIAN) CM

DEC 14 2015

Received
KANSAS CORPORATION COMMISSION
DEC 21 2015
CONSERVATION DIVISION
WICHITA, KS
Form CP-2/3
no 12-30-15