

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22761-00-01
Spot: NWNESE Sec/Twnshp/Rge: 33-6S-20W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: LEWIS M Well #: 1
County: ROOKS Total Vertical Depth: 3694 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 4925 GREENVILLE AVE., SUITE 915
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3693		200 SX
SURF	8.625	209		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2015 2:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC LLC Phone: (620) 755-2571

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1806' w/300 sx cement.
Production perforations: 3489' - 3638'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2015 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3600' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2240' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 840' and pumped 65 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2' annulus and pressured up immediately to 200 psi.
GPS: 39.48735N -099.55029W

Perfs:

Top	Bot	Thru	Comments
3636	3638		
3489	3491		

Remarks: QUALITY WELL SERVICE TICKET # 6441

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

DEC 21 2015

Received
KANSAS CORPORATION COMMISSION

DEC 30 2015
CONSERVATION DIVISION
WICHITA, KS

no
12.30-15
Form CP-2/3