

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-21583-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 20-17S-14W  
1650 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: DIRREEN Well #: 3  
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3397       |             | 75 SX    |
| SURF   | 8.625 | 881        |             | 400 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2015 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GAYLARD UNRUH Company: PROSPECT OIL AND GAS Phone: (785) 483-1426

Proposed  
Plugging  
Method:

Ordered 13 sx gel followed by 400 sx 60/40 pozmoix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/09/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 800'. Ran tubing to 3380' and pumped 13 sx gel followed by 50 sx cement. Pulled tubing to 1500' and pumped 70 sx cement. Pulled tubing to 800'. Circulated cement to surface w/105 sx cement. Shut valve on casing and circulated cement to surface on surface pipe w/30 sx cement. Pulled tubing and topped off w/10 sx cement.

GPS: 38.56012 -098.89149

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3397 | 3400 |      |          |

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

cm

Received  
KANSAS CORPORATION COMMISSION

DEC 21 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

DEC 14 2015

*no*  
*12.30.15*