

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-21159-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056 ^{6/98}
(owner/company name) (operator's)
ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita
STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481
LEASE CUMMINS WELL# 1-15 SEC. 15 T. 24S R. 15 (~~East~~ West)

C - SE - NE SPOT LOCATION/OOOO COUNTY Stafford
3300 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 343' KB CEMENTED WITH 250 SACKS
PRODUCTION CASING SIZE 4 1/2" SET AT 4268' KB CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4160-4164' (16 holes) Simpson Sand
ELEVATION 2026' KB T.D. 4273' PBTD 4224' ANHYDRITE DEPTH 961
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thom Pool PHONE# (316) 995-3171 (Belpre Office)
793-0289 (Cell Phone)

ADDRESS P.O. Box 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893 ^{6/98}
(company name) (contractor's)

ADDRESS P.O. Box 847 Pratt, Kansas 67124 PHONE # (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/8/97 AUTHORIZED OPERATOR/AGENT: W. Byron Billman
(signature)



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 10, 1997

F G Holl Company LLC
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cummins #1-15
API 15-185-21,159
3300 FSL 660 FEL
Sec. 15-24S-15W
Stafford County

Dear Thom Pool,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-185-21159

WELL LOG - - - - - CUMMINS #1-15
Located: C SE NE, Section 15-24S-15W, Stafford County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 1, 1980
COMPLETED: November 7, 1980

TOTAL DEPTH: 4270'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 75 Surface Soil, Sand	Ran 8 joints used 8 5/8", 28# casing. 330.58' set at 343' K.B. Cemented with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 8:00 PM, 11-1-80, by Howco.
75 - 345 Clay, Shale	
345 - 720 Shale, Sand, Red Bed	
720 - 970 Red Beds	
970 - 988 Anhydrite	
988 - 1883 Shale	
1883 - 4270 Lime and Shale	Ran 12 joints used 10 5/8", 4 1/2" casing and 120 joints new 10 5/8", 4 1/2" OD casing, 4257.83' set at 4268' K.B. Cemented with 100 sacks Lite and 150 sacks 50/50 Pozmix, 18% salt, 3/4 of 1% QFR-2, 5# gilsonite per sack, 1/4# nylon fiber per sack, 1/8# flo seal per sack. 250 gal, mud flush and 20 bbls. salt flush. Plug down at 11:45 AM, 11-7-80, by Howco.

15-185-21159
STERLING DRILLING COMPANY

Deviation Surveys: 1° at 2089'
2° at 4250'