

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-185-20,875 ✓ (of this well)
Lease Owner Zenith Drilling Corporation
Address 505 Fourth Financial Center, Wichita, Kansas 67202
Lease (Farm Name) O'Connor (Washdown) Well No. 1
Well Location NW SW Sec. 18 Twp. 24 Rge. 15 (E) (W)
County Stafford Total Depth 4360' Field Name
Oil Well X Gas Well Input Well SWD Well Rotary D & A
Well Log attached with this application as required yes
Date and hour plugging is desired to begin January 12, 1981

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Hazlip Address 209 S. Pine, Pratt, Kansas
67124
Plugging Contractor PIPE RECOVERY COMPANY License No. 868
Address Box 486, Ellinwood, Kansas 67526

Invoice covering assessment for plugging this well should be sent to:

Name Zenith Drilling Corporation
Address (shown above)

and payment will be guaranteed by applicant or acting agent.

Signed: Evelyn Roth
Applicant or Acting Agent

Date: January 9, 1981

198
JAN 13 1981
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



JOHN CARLIN
C. LOUX
ANE T. ROY
PHILIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Bldg.
WICHITA, KANSAS 67202

January 13, 1981

WELL PLUGGING AUTHORITY

Well No.	1
Lease	O'Conner (Washdown)
Description	NW SW
Section	18-24S-15W
County	Stafford
Total Depth	4360'
Plugging Contractor	Pipe Recover Company


Zenith Drilling Corporation
505 Fourth Financial Center,
Wichita, Kansas, 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.


Yours very truly,


For Administrator

Mr. Duane L. Rankin, P.O. Box 967, Great Bend, Kansas, 67530
is hereby assigned to supervise the plugging of the above named well.

KANSAS DRILLERS LOG
 No. 15 — 185 — 20,875
 County Number

S. 18 T. 24 R. 15 W
 Loc. C NW SW
 County Stafford
 640 Acres



Locate well correctly
 Elev.: Gr. 2048'
 DF KB

Operator
 Murfin Drilling Co.
 Address
 617 Union Center Wichita, Kansas 67202
 Well No. #1-18 Lease Name O'Connor
 Footage Location
 660 feet from (N) &X line 600 feet from (W) line of narrow SW/4
 Principal Contractor Geologist
 Murfin Drilling Company Charles Spradlin
 Spud Date Total Depth P.B.T.D.
 12-4-78 4350'
 Date Completed Oil Purchaser
 12-15-78 None

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf. Csg.	12 1/4	8 5/8	24#	605'	60-40 Poz Common	250 200	2% Gel, 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)
 RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
 bbls. MCF bbls. CFPB
 Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Murfitt Drilling Company

DESIGNATE TYPE OF FORM: OIL, GAS,
DRY HOLE, ETC.

Dry Hole

Well No.

Lease Name

1-18

O'Connor

S 18 T 24 R 15 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay & Sand	0	85	ANHYDRITE	1015'
Sand, Shale & Lime	85	605	B/FLORENCE	2357'
Shale & Red Beds	605	1575	COTTONWOOD	2619'
Shale & Lime	1575	1990	NEVA	2640'
Lime & Shale	1990	2410	RED EAGLE	2710'
Lime	2410	2605	AMERICUS	2814'
Lime & Shale	2605	2953	WOOD SIDING	2885'
Lime	2953	3105	STOTLER	3008'
Lime & Shale	3105	3840	TARKIO	3063'
Lime	3840	4350	TOPEKA	3213'
		RTD	HEEBNER	3613'
			LANSING	3757'
			B/KC	4051'
			VIOLA	4206'
			SIMPSON	4306'
			TD	4350'

STATE OF KANSAS
JAN 13 1981
CONSERVATION DIVISION
Topeka, Kansas

DST #1: 3876-3900'/30-30-30-30. Wk blo - died in 5", Flushed-no help, rec 60' VSOSpM.
FP: 50/50-50/50#, SIP: 1176-1079#.

DST #2: 4122-4226'/30-45-90-120. GTS/20". 1st: 12.7/25"; 12.7/30". 2nd: 47 1/5"; 40.9/10";
32.6/15"; 37.6/25"; 30.4/35"; 32.4/45". rec. 125' SLGCM. FP: 100/100-100/125#,
SIP: 1297-1302#.

DST #3: 4228-96'/30-30-45-60. Rec. 120' GIP, 60' M. FP: 75-75#; SIP: 117-150#

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Larry M. Jack
Signature
Larry M. Jack, Production Manager

Title

December 28, 1978

Date