

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

Rec'd  
RECEIVED  
STATE OF KANSAS CORPORATION COMMISSION  
7-17-98  
FORM-CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

Wichita, Kansas

API # 15-185-23042-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056

(owner/company name) (operator's)  
ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE YOUNG WELL# 3-18 SEC. 18 T. 24S R. 15 (East/West)

- SW - SE - SW SPOT LOCATION/OQQO COUNTY Stafford

330 FEET (in exact footage) FROM 8/N (circle one) LINE OF SECTION (NOT Lease Line)

3630 FEET (in exact footage) FROM 8/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE NA SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 8 5/8" SET AT 236' KB CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4459' KB CEMENTED WITH 320 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs @ 3895 - 3898'

ELEVATION 2055' KB T.D. 4485' PBD 4425' ANHYDRITE DEPTH 1003  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Shoot off casing and remove. Set intermediate and top  
plugs through casing as specified by KCG representative.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?           

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (316) 793-0915

ADDRESS P.O. Box 158 City/state Belpre, Kansas 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893

(company name) (contractor's)  
ADDRESS P.O. Box 847 Pratt, Kansas 67124 PHONE # (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-16-98 AUTHORIZED OPERATOR/AGENT: W. Bryce Bidleman

(signature)

W. Bryce Bidleman



## *Kansas Corporation Commission*

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

July 20, 1998

F.G. Holl Company, L.L.C.  
6427 E. Kellogg, PO Box 780167  
Wichita, Ks. 67278-0167

Young #3-18  
API 15-18523042  
SW SE SW  
Sec. 18-24S-15W  
Stafford County

Dear F.G. Holl Co.,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888

JUL 17 1997

**Sterling Drilling Company, Rig #4**

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

API# 15-185-23042,0000

Young 3-18

LOCATION: C Sw Se Sw

Section 18 T 24s R 15W  
Stafford County, Kansas

OWNER: F.G. Holl Company L.L.C.  
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 02-Jan-97  
COMPLETED: 09-Jan-97

TOTAL DEPTH: DRILLER 4485 FEET ELEVATIONS: G.L. 2046  
LOGGER 4485 FEET K.B. 2055

LOG

0 - 150 FEET Surface soil and sand  
150 - 240 FEET Redbeds and blue shale  
240 - 1795 FEET Shale and Redbeds  
1795 - 4485 FEET Lime/Shales/Dolomite

CASING RECORDS

Spud @ 7:45 am on 1-2-97. Drilled 240' 12-1/4" hole, ran 6 jts 24# 8-5/8" casing. 224.07' set at 236' KB. Cement with 225 sx. 60/40 Poz, 2% Gel, 3% CC. Plug down at 12:45 pm on 1-2-97 by HOWCO, Ticket # 104935. Good Returns.

Ran 108 jts 4-1/2" casing. 83 jts New, 25 jts Used. Used on bottom. Tallied 4450.44' set @ 4459' KB. Cemented with 70 sx lite & 250 sx FG Holl mix. Plug down @ 11:00 am on 1-9-97 by HOWCO. Plugged rathole with 15 sx and mousehole with 10 sx. Ticket # 104967. Centralizers on jts # 1,10,17,25,35.

DEVIATION SURVEYS

1/4 DEG. @ 240 FEET  
1-1/2 DEG. @ 3800 FEET  
3/4 DEG. @ 4485 FEET