

Form CP-3
Rev. 6-26-62

N
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1963
9-20-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wilcox Oil Inc.

Complete Address: P. O. Box 13528, Phoenix, Arizona

Lease Name Reaves Well No. # 1

Location SW SW NW Sec. 1 Twp. 24 Rge. 16 (E) (W)

County Edwards Total Depth 4000

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 East Sixth, Ellinwood, Kansas License No. 396

Operation Completed: Hour 4:00PM Day 18th Month Sept. Year 1963

The Above well was plugged as follows:

315' of 10 3/4" surface pipe, cement circulated. 3974' of 6 5/8" drill
pipe for long string, cemented with 125 sacks. Plugged back to 3865'.
Top perforation 3691'. Bottom hole was cemented with 5 sacks, at 3670',
on plug and rock bridge. Plug was pushed to 275', 10' rock bridge,
hole was bailed down and 30 sacks cement put on plug. Hole was filled
with mud to 40', 10' rock bridge, cemented with 15 sacks to base cellar.
2368' of 6 5/8" drill pipe for long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/20/63
INV. NO. 7968-W

Signed: Archie Elving
Well Plugging Supervisor