

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION  
11-12-63  
NOV 12 1963CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Wilco Oil Inc.Complete Address: Box 13528, Pheonix, ArizonaLease Name Bright Well No. # 1Location NW NW SW Sec. 1 Twp. 24 Rge. 16 (E) (W) WCounty Edwards Total Depth 3984Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     Other well as hereafter indicated:     Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 East Sixth, Ellinwood, Kansas License No. 396Operation Completed: Hour 11:30AM Day 9th Month Nov. Year 1963

The Above well was plugged as follows:

356' of 10 3/4" surface pipe, cemented to top. 3983' of 5 1/2" long string,  
cemented with 125 sacks. Top perferation 3654'. Bottom of hole was sanded  
to 3600', and cemented with 5 sacks. Fluid level was up in hole. 6 sacks  
cement was mixed in barrel and put on plug, through dump bailer, and let  
set over night. Next morning hole bailed down and 19 sacks cement was added  
to plug, which was set at 275', bridged with 10' rock. Hole was filled with  
mud to 35', 10' rock bridge, cemented with 10 sacks to base cellar.  
2400' of 5 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/12/63INV. NO. 8094-WSigned: Archie Elving  
Well Plugging Supervisor