

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Inc. has this
date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman

Complete Address: 1714 First National Bldg., Tulsa, Oklahoma

Lease Name: Cooper Well No. # 1

Location: NE NE NE Sec. 28 Twp. 29 Rge. 14 (E)(W) W

County Pratt Total Depth 4582' 011 Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

798' of 8 5/8" surface pipe, cement circulated with 450 sacks.

Fill hole with drilling mud to 790', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent