



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
April 15, 1979

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

5-1-79
RECEIVED
STATE CORPORATION COMMISSION
MAY - 1 1979
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. C. Ray Rice of Sterling Drilling Co. has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Brown "A" Well No. 2

Location: C NW SE Sec. 1 Twp. 22 Rge. 10 (E) (W) X

County: Renov Total Depth 3165' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through
drill pipe at 500'. Pump 25 sacks cement through
drill pipe at 210'. Push plug and 1/2 sack hulls
to 40' and cap hole with 10 sacks cement.
Bridge rathole and cement with 2 sacks cement.
8 3/8" - 218' cement circulated

Very truly yours,

[Signature]
Conservation Division Agent