

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 NOV 26 1967  
 11-20-67  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Nov. 2, 1967

Dear Sir:

Mr. Russell Hobercht of Russ Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Hobercht guarantees payment of the plugging fee.

Operator's full Name: Alkay Oil Co.

Complete Address: R. R. #2 Great, Bond, Kansas.

Lease Name: Kendall Well No. #1

Location: NE-SW-SE Sec. 2 Twp. 24 Rge. 13W(E) (W) W

County Stafford Total Depth 4046' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Hobercht was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, circulated with 150 sacks  
cement. 3862' of 4 1/2" pipe. 125 sacks. Plug 3610' Top  
perforation at 3554'. Sand to 3525' & 4 sacks. Mud to  
200', 10' rock bridge, 25 sacks cement Mud to 40', 10'  
rock bridge, 10 sacks cement to base of cellar.

Very truly yours,

*Herman Justice*  
 Conservation Division Agent