

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20890-00-00
Spot: SWNE Sec/Twnshp/Rge: 33-30S-15W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: RAY MOAD Well #: 1
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: 7572
Op Name: MURJO OIL & ROYALTY COMPANY
Address: 131 E EXCHANGE AVE STE 101 PO BO
FORT WORTH, TX 76121

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3156		WITH 2 SX CMT
CIBP		4404		
PROD	5.5	4720	900	WITH 125 SX CMT
SURF	8.625	270		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2015 11:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 3156' WITH 2 SX CMT. PLUG AT 940' WITH 15 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 11/11/2015 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 3156' WITH 2 SX CMT. 1ST PLUG AT 940' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED BUT FELL APP. 150-170'. TOPPED OFF WITH CMT. *1 1/2 yds*

Perfs:

Top	Bot	Thru	Comments
4569	4573		
4493	4495		
3206	3211		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

[Signature]
[Signature]
(TECHNICIAN)

RECEIVED
NOV 19 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

DEC 04 2015
CONSERVATION DIVISION
WICHITA, KS