

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-16653-00-00
Spot: S2NE Sec/Twnshp/Rge: 26-32S-11W
1980 feet from N Section Line, 1320 feet from E Section Line
Lease Name: STONE D Well #: 1
County: BARBER Total Vertical Depth: 4461 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4460	2440	WITH 100 SX CMT
SURF	8.625	250		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/04/2015 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 150# HULLS ON BOTTOM. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 12/04/2015 5:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PUMP 30 SX CMT WITH 150# HULLS FOR BOTTOM PLUG. 1ST PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4423	4438		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 09 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
DEC - 8 2015
KCC DODGE CITY

Form CP-2/3