

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-20346-00-01
Spot: W2NWNE Sec/Twnshp/Rge: 15-31S-21W
4619 feet from S Section Line, 2250 feet from E Section Line
Lease Name: BERRYMAN Well #: 15-2-2
County: CLARK Total Vertical Depth: 6384 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	6350	2550	WITH 150 SX CMT
SURF	8.625	622		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT & 150# HULLS ON BOTTOM. PLUG AT 1180' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/19/2015 4:40 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 30 SX CMT WITH 150# HULLS ON BOTTOM. PRESSURED TO 1500#. 1ST PLUG AT 1180' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6056	6066		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

12/18/15 CLKM

District: 01

Signed *[Signature]*

JA

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

RECEIVED
DEC - 7 2015
KCC DODGE CITY

DEC 09 2015

CONSERVATION DIVISION
WICHITA, KS