

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-20659-00-02  
Spot: SWNE Sec/Twnshp/Rge: 2-31S-21W  
3303 feet from S Section Line, 2026 feet from E Section Line  
Lease Name: BIRNEY Well #: 2-7RE  
County: CLARK Total Vertical Depth: 5346 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 124 N MAIN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5304	2280	WITH 350 SX CMT
SURF	8.625	530		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2015 7:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 200# HULLS. PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. PLUG AT 580' WITH 50 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/02/2015 10:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 30 SX CMT WITH 150# HULLS ON BOTTOM. 1ST PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5232	5240		
5204	5210		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

EMZ  
512

Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

RECEIVED  
DEC - 7 2015  
KCC DODGE CITY

DEC 09 2015  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3