

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20789-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 18-6S-22W
383 feet from S Section Line, 5269 feet from E Section Line
Lease Name: GRIFFEY Well #: 1
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2052		500 sx
SURF	8.625	246		160 SX

Well Type: SWD UIC Docket No: D25828.0 Date/Time to Plug: 11/13/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/200 # hulls.
Perforations: 1750' - 1770'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2015 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1806' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 950' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing. Squeezed 4 1/2" casing w/20 sx cement at 1000 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 15 sx cement. Backside standing full of cement.

GPS: 39.52565N -099.82495W

Perfs:

Top	Bot	Thru	Comments
1750	1770		

Remarks: CONSOLIDATED TICKET # 46626

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 09 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

12/18/15 cm

UICV