

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20256-00-00
Spot: NESWSE Sec/Twnshp/Rge: 16-14S-10W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BAKER A Well #: 2
County: ELLSWORTH Total Vertical Depth: 3171 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3171		250 SX
SURF	8.625	266		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2015 12:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 11/24/2015 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1250', 900', AND 310'. RUN TUBING TO 3111' AND PUMP 100 SX'S CEMENT WITH COTTON HULLS. PULL TUBING TO 2100' AND PUMP 100 SX'S WITH COTTON HULLS. PULL TUBING TO 1250' AND ATTEMPT TO CIRCULATE CEMENT TO SURFACE. DID NOT CIRCULATE. COME BACK ON 11-24-2015, TAGGED CEMENT AT 1950'. RUN TUBING BACK TO 1950' AND PUMP 150 SX'S CEMENT, PULL TUBING TO 900' AND CIRCULATED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 350 SX'S ON 11-23-15 AND 225 SX'S ON 11-24-15.

Perfs:

Top	Bot	Thru	Comments
2850	2948	CSG	

Remarks: PERF TECH #13079. QUALITY OILFIELD CEMENT #1450 ON 11-23-15. QUALITY OILFIELD #1926 ON 11-24-15. DENIED TA 10 YEAR

Plugged through: TBG

12/18/15 CKM

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 14 2015
CONSERVATION DIVISION
WICHITA, KS

1/24