

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20994-00-00
Spot: NWSEWNWE Sec/Twnshp/Rge: 21-14S-10W
4405 feet from S Section Line, 1842 feet from E Section Line
Lease Name: VOPAT D Well #: 14
County: ELLSWORTH Total Vertical Depth: 2975 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2926		50 SX
SURF	8.625	453		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2015 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUCHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/02/2015 12:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1250', 900', AND 500'. RUN TUBING TO 2867' AND PUMP 150 SX'S WITH COTTON HULLS. PULL TUBING TO 1450' AND PUMP 100 SX'S WITH COTTON HULLS, GOT CIRCULATION OUT OF 5.5", PULL TUBING TO 500' AND CIRCUALTE CEMENT TO SURFACE OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2856	2874	CSG	

Remarks: PERF TECH #13019. QUALITY OILWELL CEMENT TICKET #7301. OPERATOR WAS SENT THE TA - N.O.V. LETTER.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)
KCC WICHITA

12/18/15 CKM

DEC 08 2015

Form CP-2/3

RECEIVED