

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19774-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 22-24S-12E
3600 feet from S Section Line, 600 feet from E Section Line
Lease Name: TEXAS JOHNSON Well #: 10
County: GREENWOOD Total Vertical Depth: 1734 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.875	1715		125 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2015 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: RANDALL L. TRIMBLE Company: _____ Phone: (620) 836-2000

Proposed Plugging Method: 3 perfs at 455. 3 perfs at 250. 20 sack plug at 1,515. 20 sack 455. At 250 circulate to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2015 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1517' pumped 25 sxs cement, pulled tubing to 475' pumped 20 sxs cement, pulled tubing to 253' pumped 65 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
DEC 14 2015
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

12/18/15 CKM

District: 03

Signed Miko Welfer
(TECHNICIAN)

KCC WICHITA

DEC 17 2015

RECEIVED

15-073-197740000

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. 2641
Foreman Rick Ledford
Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-2-15	1000	Texas # 10	23	24	12	SW	Ks
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Trimble & Macloskey Oil LLC	Box 171	Gridley	Ks	66852	RL SB KR	105	Sherron F.
						112	Chris B.
						145	Kevia M.

Job Type P.T.A Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. 14 # Drill Pipe _____
 Casing Size & Wt. 7" Cement Left in Casing _____ Water Gal/SK 7.0 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting- Rig up to 2 3/8" tubing. Pumped 400 gal. spacers ahead. Plugging orders as follows:

- 25 sks @ 1517'
- 90 sks @ 475'
- 65 sks @ 253'

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C203	110 sks	100/40 Pozmix cement	12.75	1402.50
C206	380 #	40% gel	.20	76.00
C108A	4.73	tan mileage bulk tank	m/c	345.00
C113	3 hrs	80 Bbl VAC. TRK	85.00	255.00
C224	3300 gals	city water	10.00/1000	33.00
KCC WICHITA				
DEC 17 2015				
RECEIVED				
			Subtotal	2920.75
			Sales Tax	7.57
Authorization witnessed by <u>Brian Macloskey</u> Title <u>Co. Rep.</u>				Total

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.