

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20693-00-00  
Spot: SESWNESE Sec/Twnshp/Rge: 36-28S-23W  
1379 feet from S Section Line, 712 feet from E Section Line  
Lease Name: MCCARTY Well #: 1-36  
County: FORD Total Vertical Depth: 5450 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5433	2670	WITH 175 SX CMT
SURF	8.625	649		WITH 415 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2015 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT WITH 150# HULLS ON BOTTOM. PLUG AT 1530' WITH 10 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/16/2015 5:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 25 SX CMT WITH 150# HULLS ON BOTTOM. 1ST PLUG AT 1530' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5256	5258		
5253	5255		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

12/18/15 CKM

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
DEC - 7 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

DEC 09 2015  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3