

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20968-00-00  
Spot: SESESESW Sec/Twnshp/Rge: 3-28S-23W  
100 feet from S Section Line, 2634 feet from W Section Line  
Lease Name: RIEGEL Well #: 2-3  
County: FORD Total Vertical Depth: 5139 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	645		WITH 250 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2015 9:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: GALEN ROACH Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 11/19/2015 12:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY WELL SERVICE.

Plugged through: DP

12/18/15 ckm

District: 01

Signed Eric MacLaren  
SA (TECHNICIAN)

RECEIVED  
DEC - 8 2015  
KCC DODGE CITY

KCC WICHITA

Form CP-2/3

DEC 11 2015

RECEIVED