

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23436-00-00
Spot: S2NWSENE Sec/Twnshp/Rge: 18-18S-26W
3592 feet from S Section Line, 924 feet from E Section Line
Lease Name: HERL A Well #: 1
County: NESS Total Vertical Depth: 4652 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4652	0	WITH 125 SX CMT
SURF	8.625	259		WITH 135 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2015 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-5101

Proposed Plugging Method: PUMP 50 SX CMT WITH 275# HULLS IN PERFS. RTIH TO 2050' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/20/2015 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 50 SX CMT WITH 275# HULLS. RAN TBG TO 2050' & CIRCULATED CMT TO SURFACE WITH 110 SX CMT. PULLED TBG & TOPPED OFF WITH 20 SX CMT. PRESSURED BACKSIDE TO 500# WITH 0 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4585	4589		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

12/18/15 *cm*

District: 01

Signed *E. MacLaren*
(TECHNICIAN)

RECEIVED
DEC - 7 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

DEC 09 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3