

2 050198

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-21,025-0000

~~SE~~/SW SEC. 7, T 22 S, R 9 W/2

2970 feet from N/S section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Drake Well # 1

Operator Name & Address Zenith Drlg. Corp

County Reno 119.93

Suite 505

Well Total Depth 3690 feet

4th Financial Center

Conductor Pipe: Size - feet -

Wichita, Ks. 67202

Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor Sterling Drlg. Co. License Number -

Address Sterling Drlg. Co.

Company to plug at: Hour: 1:00 PM Day: 16 Month: Nov. Year: 19 84

Plugging proposal received from -

(company name) - (phone) -

were: 35 sx. Cement @ 3684

35 sx. " " 321

15 sx. " " 40

10 sx. " Rat hole

Plugging Proposal Received by Steve VanGieson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part - None -

Operations Completed: Hour: 4:15 P. Day: 16 Month: Nov. Year: 19 84

ACTUAL PLUGGING REPORT Fill hole with mud. Run Drlg. pipe to 3684 ft. & spot 35 sx. Cement, Disp. with mud.

Pull Drlg. Pipe to 321 & spot 35 sx. Cement Disp. with mud. Pull Drlg. Pipe & Push 1/2 sx. huls & plug to 40 ft. & fill to surface with Cement. Circulate 10 sx. Cement in Rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1984

Remarks: Howco ticket # 918372

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this ticket, Kansas

I () () did not) observe this plugging.

11-26-84

DATE 12-4-84

Signed Glen W. Ward
(TECHNICIAN)

INV. NO. 5793

Starting Date: 11 15 84
month day year

API Number 15- 155-21,025

OPERATOR: License # 5141
Name ZENITH DRILLING CORPORATION
Address Suite 505 Fourth Financial Center
City/State/Zip Wichita, Kansas 67202
Contact Person Sherrill Compton, Vice Pres.
Phone (316) 265-6697

SE SW NW Sec 7 Twp 22 S, Rge 9
(location)
2970 Ft North from Southeast Corner of Section
4290 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5142
Name Sterling Drilling Company
City/State Sterling, Kansas

Nearest lease or unit boundary line 330 feet.
County Reno
Lease Name Drake Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 150 200 mhc feet
Lowest usable water formation Unknown
Depth to Bottom of usable water 175 220 mhc feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200 220 feet
Conductor pipe if any required None feet
Ground surface elevation approx. 1750 feet MSL
This Authorization Expires 9-24-85
Approved By 10-24-84

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3700 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Simpson

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 10/23/84 Signature of Operator or Agent Sherrill Compton Title Vice-President
SHERRILL COMPTON

mhc/NOHE 10/24/84 Form C-1 4/84