

1 070366

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,840 500-00
50' S & 60' E
of NE SW NW, SEC. 14, T. 29 S, R. 14 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 4459

Operator: Agate Petroleum, Inc.
Name & Address 1301 Fourth National Bank Bldg.
Tulsa, OK 47119

3580 feet from S section line
4230 feet from E section line

Lease Name Luther Well # 1

County Pratt

Well Total Depth 4720 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 5:30 a.m. Day: 4 Month: 7 Year: 19 87

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 815-835'

1st plug at Arbuckle with 50 sx cement, 2nd plug at Anhydrite with 50 sx cement,

3rd plug at 30' below base of surface pipe with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 a.m. Day: 4 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement,

2nd plug at 350' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1987
7-7-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

(check) id both observe this plugging.

DATE 7-7-87

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 17434