

To: 1090247 1-22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-22,095-00-00 55R
S/2 SE NE, SEC. 14, T 29 S, R 14 W/EX
2970 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5135
Operator: John O. Farmer, Inc.
Name & Address: P.O. Box 352
Russell, KS 67665

Lease Name Randle Well # 1
County Pratt 150.15
Well Total Depth 4620 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 2 a.m. Day: 22 Month: 1 Year: 19 93

Plugging proposal received from Kelly Branum
(company name) Emphasis Oil Operations (phone) 913-483-3518

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 790'
1st plug at 800' with 50 sx cement, 2nd plug at 345' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 a.m. Day: 22 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement,
2nd plug at 345' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
1-26-93
JAN 26 1993
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(did not) observe this plugging.

DATE 2-4-93

INV. NO. 37302

Signed [Signature] (TECHNICIAN)