

1 010241

MAY 14 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,833 - 00-00
C NW SE, SEC. 13, T 29 S, R 14 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5237
Operator: Plano Petroleum Corporation
Name & Address: P.O. Box 247
Plano, TX 75074

Lease Name Schrepel Well # 3
County Pratt 150.64
Well Total Depth 4635 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5:30 a.m. Day: 14 Month: 5 Year: 1987

Plugging proposal received from Gary Bagby

(company name) Abercrombie Drilling Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1974' GL
Anhydrite 802-823'

1st plug at base of Arbuckle with 20 sx cement, 2nd plug at 825' with 50 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 7:30 a.m. Day: 14 Month: 5 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 825' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COM.

15-22-87

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this form.)
(did / observe this plugging.)

INVOICED

DATE 5-18-87

Signed Jack R. Luthi
(TECHNICIAN)

INV. NO. 16945