

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20116-00-00
Spot: CE2NESW Sec/Twnshp/Rge: 2-24S-16W
1980 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: KLEIN C Well Number: 1
County: EDWARDS Total Vertical Depth: 4050 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Conductor Pipe: Size feet: 31.63
Surface Casing: Size 8.625 feet: 318 WITH 225 SX CMT
Production: Size 5.5 feet: 4046 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/24/2002 2:30 PM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: TIM THOMPSON Company: Phone: (620) 482-2943

Proposed Plugging Method: Tubing is parted below 3500' circulate gell to surface then mix and circulate cement to surface leaving tubing in hole.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/24/2002 4:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG PUMPED 80 SX GEL MUD TO KILL WELL. TUBING PARTED AT 3500'. 2ND PLUG PUMPED DOWN 2 3/8" TUBING AND CIRCULATED CMT FROM 3750' TO SURFACE WITH 400 SX CMT. 3RD PLUG PUMPED 100 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 200#.

RECEIVED
FEB 15 2002
2 - 15 - 02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Steve Durrant
(TECHNICIAN)

INVOICED FEB 11 2002

Form CP-2/3

DATE Feb 15-02
INV NO 2002061391

MP