

1 040373

12-6

15-047-100730000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 1964
C SE, SEC. 2, T 24 S, R 16 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Klien Well # 1

Operator: Oil Producers Inc. of Kansas
Name & Address P.O. Box 8647
Wichita, KS 67208

County Edwards 128.21

Well Total Depth 3945 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 6 Month: 12 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3775' PBD 3050' Perfs at 2451-54, 2469-72, 2528-31, 2639-42'

1st plug sand back to 2400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 6 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 11/28/89-Shot casing at 2096' and well blew in, pumped 30 sx of common cement to 2050' and shut in.

1st plug sanded back to 2400' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1789' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 12-13-89

INV. NO. 26797

Signed Stephen J. Fisher
(TECHNICIAN)

Rec'd
12-8-89

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1989

CONSERVATION DIVISION
Wichita, Kansas