

15-047-20133-0001

Docket No. D-20,531
Completed 3-19-73

R

To: 1 010064
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
S/2 SE SE, SEC. 2, T 24 S, R 16 W X

330 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5258
Operator: Messman-Rinehart Corporation
Name & Address 500 Bitting Building
Wichita, S 67202

Lease Name Klein Well # 2
County Edwards 132.15
Well Total Depth 4066 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:25 am Day: 31 Month: December Year: 19 85

Plugging proposal received from Millard Kelso
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4058' Open Hole
1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:55 am Day: 31 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 300 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2468' 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986
INV. NO. 11786

RECEIVED
STATE CORPORATION COMMISSION

Rec'd 1-13-86 JAN 13 1986

CONSERVATION DIVISION

Signed Jack R. Smith
(TECHNICIAN)