

To: 1 010067
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 7-1-66

SW NE SE, SEC. 33, T 24 S, R 15 W 26X
1650 feet from S section line
1190 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5061
Operator: Robert F. White
Name & Address: 505 Union Center
Wichita, KS 67202

Lease Name Doran Well # 1
County Stafford 144.30
Well Total Depth 4440 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:50 pm Day: 3 Month: January Year: 19 86

Plugging proposal received from Lloyd Davis

(company name) Robert F. White Consultant (phone) 316-263-7957

were: 5 1/2" at 4011' PBTD 3000' Perfs at 3897-3903'; 3799'; 3777-80'; 3795-3800'; 2923-33'
2624' 31' DV Tool at 3196' with 150 sx cement
1st plug pump 1 sack hulls and 30 sx cement to bottom and stop plug at 2600'
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:25 pm Day: 3 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement to bottom and stopped
plug at 2600', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,
1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi

Remarks: Used 60/40 Pozmix 6% gel. by Allied. Recovered 1950' 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

(did/supervisor) observe this plugging.

JAN 13 1986 Signed _____

1-13-86

CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)

INVOICED

JAN 14 1986

DATE

INV. NO. 12067