

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,577-0000

LEASE NAME Doran

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 24S RGE. 15W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3/26/90

Plugging Completed 4/3/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mid-American Hydrocarbon, Inc.

ADDRESS 114 East Avenue North Lyons, KS. 67554

PHONE# (316) 257-5111 OPERATORS LICENSE NO. 9705

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4496'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	358'	none
				5 1/2	4502	2238'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded bottom to 3850' ran 5 sacks cement. Shot pipe @3000', 2800', 2000'. Plugged with 500# hulls, 20 gel, 175 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mid-American Hydrocarbon, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

AND SWORN TO before me this 5 day of April, 19 90

Irene Herzberg
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1990
4-10-90
CONSERVATION DIVISION
Wichita, Kansas

Commission Expires:





ACOUSTIC CEMENT BOND LOG

BOND LOG

COMP. MID AMERICAN HYDROCARBON WELL NO. 2 DORAN FIELD COUNTY STAFFORD ST. KANSAS	COMPANY MID AMERICAN HYDROCARBON, INC.						
	WELL NO. 2 DORAN						
	FIELD						
	COUNTY STAFFORD	STATE KANSAS					
	API NO. 15-185-22,577	OTHER SERVICES PERF					
LOCATION 100 FT N OF E/2-E/2-SE							
SEC. 33	TWP. 24S	RGE. 15W					
PERMANENT DATUM	GROUND LEVEL	ELEV. 2031					
LOG MEASURED FROM	5 FT. ABOVE PERM. DATUM	ELEV.: K.B. 2036					
DRILLING MEASURED FROM KELLY BUSHING		D.F. G.L. 2031					
DATE & TIME LOGGED	03/27/89	TYPE OF FLUID IN HOLE					
RUN NO.	ONE	DENSITY OF FLUID					
DEPTH - DRILLER	4496	FLUID LEVEL					
DEPTH - WELEX	4455 ←	CEMENT TOP EST. - LOGGED					
BTM. LOGGED INTERVAL	4444	EQUIPMENT & LOCATION					
TOP LOGGED INTERVAL	3700	RECORDED BY					
MAX TEMP. DEGREE	121	WITNESSED BY					
CEMENTING DATA	SURFACE STRING	PROTECTION STRING					
DATE/TIME CEMENTED							
PRIMARY/SQUEEZE	STATE OF KANSAS	PRIMARY					
EXPECTED COMP. STRENGTH	JAN 9 1989						
CEMENT VOLUME		135 SX					
CEMENT TYPE/WEIGHT FORMULATION	CONSERVATION DIVISION Wichita, Kansas	50/50POZ SALT SAT. .75 PCT CFR3					
MUD TYPE/MUD WEIGHT							
RUN NO.	BOREHOLE RECORD			CASING AND TUBING RECORD			
	BIT	FROM	TO	SIZE	WGT.	FROM	TO
ONE	12.25	0	358	8.625	24	0	358
TWO	7.875	358	4510	5.5		0	4502