

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 33 Twp. 24S Rge. 15W E&W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NE NE NW

Lease Owner Barnett Oil Company
Lease Name Doran Well No. 1

Office Address 1625 Vickers KSB&T Bldg.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed September 7 1978
Application for plugging filed September 7 1978
Application for plugging approved September 7 1978
Plugging commenced September 7 1978
Plugging completed September 7 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William Owens - Pratt
Producing formation Depth to top Bottom Total Depth of Well 4315
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged hole as follows: Filled hole w/mud; spotted 40 sx
cement @ 540'; mud to 330' spotted 40 sx; mud to 40'; wood
plug & 1/2 sx hulls for solid bridge - 12 sx to base of
cellar - 3 sx in rat hole - completed at 5:00 p.m. by Allied
on 9-7-78;

RECEIVED
STATE CORPORATION COMMISSION

Rec'd
9-12-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
800 Bitting Building, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1978


[Signature]
Geraldine Stewart Notary Public.

My commission expires January 12, 1981

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1978

CONSERVATION DIVISION
Wichita, Kansas





800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

September 11, 1978

WELL LOG - - - - -Doran #1
Located: NE NE NW of Sec. 33-24S-15W, Stafford
County, Kansas.

OWNER: Barnett Oil Company
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: August 31, 1978
COMPLETED: September 7, 1978

Rotary Total Depth: 4315'

<u>LOG</u>	
0 - 340	Sand, soil & shale
340 - 530	Sand & shale
530 - 570	Sand
570 - 1037	Shale & sand
1037 - 1051	Anhydrite
1051 - 1620	Shale
1620 - 2120	Shale & shells
2120 - 3815	Shale & lime
3815 - 3960	Lime
3960 - 4230	Lime & shale
4230 - 4245	Lime
4245 - 4265	Lime & shale
4265 - 4300	Lime
4300 - 4315	Lime & Shale

CASING RECORD

Ran 8 jts, 8-5/8", 28#, 8V, used casing, tallied 331.84, set @ 339 KB w/275 sx 60/40 pozmix, 2% gel 3% cc, circulated, plug down @ 9:15 p.m. by Allied.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1978

CONSERVATION DIVISION
Wichita, Kansas

Plugged 9-7-78