

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15047-00096-0000

LEASE NAME Hahn

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

990 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR Rockhold Engineering, Inc.

SEC. 4 TWP. 24 RGE. 16 (E) or (W)

ADDRESS Box 698, Great Bend, Ks. 67530

COUNTY Edwards

PHONE (316) 792-2506 OPERATORS LICENSE NO. 5111

Date Well Completed 1-1-54

Character of Well Oil

Plugging Commenced 6-13-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-12-90

Did you notify the KCC District Office prior to plugging this well? Yes

Which agent did you notify? Duane Rankin

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 4496'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	232'	None
				5-1/2"	3851'	2522.64'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3720' and 5 sacks cement. Shot casing at 3100' and 2500'. Pulled 81 joints. of 5-1/2" casing. B.J. Service plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 250 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of April, 1990

My Commission Expires:
James M. Leatherman
 Notary Public

STATE OF KANSAS
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

Rec'd
 4-18-90