

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Edwards County. Sec. 4 Twp. 24 Rge. (E) 16 (W)

Location as "NE/CNW%SW%" or footage from lines SE - SW - NW

Lease Owner Branine - Holl

Lease Name Doll Well No. 1

Office Address 6427 East Kellogg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 6 - 20 1956

Plugging completed 6 - 27 1956

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	230	8 5/8"		
		0	4251	5 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Perforations 4201 - 4214

" 3785 - 3788

Lane Wells plug set @ 3814

Filled hole with sand from 3814 to 3775 - dumped 5 sks cement - squeezed well with 25 sks Jell mud and 76 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236

Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. James G. Gould (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James G. Gould

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 56

My commission expires August 5, 1957

Mary E. Lacey, Notary Public. STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC. 4 T. 24 R. 16W  
BOOK PAGE 73 LINE 28

AUG 2 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS  
Rec'd 8-3-56

SCHAFFER DRILLING CO.

OFFICE OF THE PRESIDENT

PEOPLES BANK BUILDING

PRATT, KANSAS

WILLIAM SCHAFFER  
PRESIDENT

PHONE  
842

Driller Log  
Doll #1  
Edwards, County, Kansas

0-228	Sand, Clay, Shale
228-1000	Shale
1000-1070	Shale and Red Bed
1070-1105	Anhydrite
1105-1955	Shale
1955-2050	Shale and Lime Shells
2050-2070	Lime
2070-2241	Shale and Lime
2241-2355	Shale and Lime Shell
2355-2700	Lime and Shale
2700-3040	Shale
3040-3970	Shale and Lime
3970-4255	Lime
4255	TOTAL DEPTH

I certify that the above drillers log is true and correct as taken directly from the daily drilling reports of the Doll #1:

Low Jean Luthridge  
Schafer Drilling Co.

State of Kansas: County of Pratt:SS

The above was subscribed and sworn to before me this 21st day of October, 1955.

Maudie B McBride  
Notary Public

My commission expires 6-30-59

PLUGGING			
FILE SEC.	4	T.	24 R/16W
BOOK	PAGE	73	LINE 28

RECORDED  
STATE DEPARTMENT  
JAN 1956  
CONSULTATION DIVISION  
Wichita, Kansas