


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 31 Twp. 24 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Aylward Drilling Company
Lease Name Eichenberger Well No. 1
Office Address 909 1st Nat'l Bank Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 17 19 63
Application for plugging filed August 17 19 63
Application for plugging approved August 17 19 63
Plugging commenced August 17 19 63
Plugging completed August 17 19 63
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4335 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 260'
Plug set at 260' with 20 sacks cement
Filled with mud to 40'
Bridged plug and 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1963
12-23-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. Aylward (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
909 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1963

My commission expires December 11, 1965

[Signature] DUANE JESSUP Notary Public.



EICHENBERGER "A" #1

Casing Record: 8 5/8" - 250'
 Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company
 Location: NE NE NE, Sec. 31-24-15W, Stafford County, Kansas
 Commenced: August 6, 1963
 Completed: August 17, 1963
 Elevation: 2052 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Sand	0	175	Set 8-5/8" surface pipe @ 250' w/200 sacks cement.	
Shale	175	275		
Shale & Red Bed	275	1200	Geological Tops:	
Shale & Shells	1200	2000		
Shale & Lime	2000	2160		
Lime & Shale	2160	3375		Heabner 3678
Shale	3375	3540		Toronto 3698
Shale & Lime	3540	3630		Douglas 3715
Lime & Shale Streaks	3630	3688		Brown Lime 3822
Lime & Shale	3688	3785		Lansing 3832
Lime	3785	4096		B/Kansas City 4097
Lime & Shale	4096	4155		Cherokee (Possible Congl.) 4216
Lime	4155	4215		Conglomerate 4239
Lime & Conglomerate	4215	4242		Mississippian 4274
Lime	4242	4308		Kinderhook 4308
Sand	4308	4335 T.D.		R.T.D. 4335

DST 4216-42 Open 20 min.
 Rec. 10' drlg. mud
 IBHP 116#/30" - FBHP 75#/30"
 FP 17#-25#

DST 4278-4310 Open 1 hr.
 Rec. 65' drlg mud w/few specs oil
 IBHP 391#/30" - FBHP 149#/30"
 FP 41#-66#

No log run.

RECEIVED
 STATE CORPORATION COMMISSIONER

DEC 23 1963

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 6th day of September, 1963

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1965