

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,985-0000

LEASE NAME Debusk

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Haven Energy Corporation

ADDRESS 7310 E. Kellogg
Wichita, Kansas 67208-1695

PHONE#(310 689-4407 OPERATORS LICENSE NO. 3646

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	275'	none
				4-1/2"	4458'	2887'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4130' and 4 sacks cement. Shot pipe @3027', 2887',

pulled a total of 87 joints of 4-1/2" casing. Plugged surface with 10 gel, 4 hulls,

50 cement, 10 gel, 1 hull, released plug and 125 cement, 65/35pos, 2% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling Inc. License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Mike Kelso

Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1988

Jane Stover
Notary Public

My Commission Expires:



15AR - 9 1988
3-9-88
Form CP-4
Revised 07-86
Wichita, Kansas