


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 25 Twp. 24S Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Natural Gas and Oil Company  
Lease Name Carpenter Well No. 1  
Office Address P. O. Box 105 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 12 - 18 19 55  
Application for plugging filed 1-25 19 61  
Application for plugging approved 1-31 19 61  
Plugging commenced 2-15 19 61  
Plugging completed 2-21 19 61  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 1-20 19 61  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Arbuckle Depth to top 4417 Bottom 4423 Total Depth of Well 4455 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	194	None
				5 1/2"	4454	3702'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole to 4400' - dumped 5 sacks cement -  
Pulled pipe - pumped in 10 sks. mud and 60  
sks. cement - let cement set - removed swedge -  
dumped 10 sks. cement on top.

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-61  
MAR 13 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Co. License #236  
Address P. O. Box 572 - Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
I, J. B. Steele, Jr. (employee of owner) ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.  
P. O. Box 105 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 61

Richard R. Beach  
Notary Public.

My commission expires July 27, 1963



**CARPENTER #1**

Operator: Natural Gas & Oil Corporation  
 Contractor: Stevens Petroleum, Inc.  
 Commencement Date: November 14, 1955  
 Completion Date: December 17, 1955

Location:  
 SW NW SW of  
 Section 19-24S-18W  
 Stafford County, Kansas

**Casing Record:**

Run 6 joints of 8-9/8" casing set at 100'. Cemented with 150 sacks common cement. Run 1st joint of 6-1/2" 10-1/4" threads casing set 1 foot off bottom. Cemented with 125 sacks of common cement.

**WELL LOG**


Surface Soil & Sand	0	150
Shale & Sand	150	200
Shale	200	350
Bedded	350	463
Anhydrite	463	485
Shale & Shale	485	1767
Shale & Limestone	1767	1995
Limestone	1995	2110
Limestone & Shale	2110	2410
Limestone	2410	2495
Limestone & Shale	2495	3550
Brown Limestone	3550	3980
Limestone & Shale	3980	3943
Limestone	3943	4170
Limestone & Shale	4170	4193
Cherty Limestone	4193	4220
Limestone	4220	4260
Limestone & Chert	4260	4270
Limestone	4270	4321
Limestone & Shale	4321	4360
Shale	4360	4414
Artesian	4414	4455
Total Depth	4455	

STATE OF KANSAS

COUNTY OF RUSSELL

SS:

I hereby certify that the above information is true and correct to the best of my knowledge.

  
 S. G. Stevens, President

SWORN AND SUBSCRIBED before me, a Notary Public, this 27th day of December, 1955.

  
 Notary Public

My Commission Expires:

April 3, 1956